

Sidewalk Landscaping Design Options Sidewalks with Curbside Parking Layout Plan & Sections

DIAGONAL PARKING REQUIRES 32" COURTESY STRIP.

2a


- FOR SIDEWALK LANDSCAPING ON SIDEWALKS W/OUT CURBSIDE PARKING PLEASE REFER TO SHEET L-1.0
- PROVIDE PATH FROM PARKING SPACE TO SIDEWALK.
 DESIGN INTENT IS TO CREATE CLEAR PAHS FROM CAR
 DOORS, WHICH MAY NICLIDE BRIVEWYS (SEE DPION C
 PLAN), MEASURE PARKING AREA BETWEEN DRIVEWAYS, RED
 ZONES, BLUE ZONES & YELLOW ZONES, AND DWIDE PARKING
 AREA EQUALLY, CREATE 4 FT. MIN. PATH IN CENTER OF
 EACH SPACE.
- REFER TO SE DEPARIMENT OF PUBLIC WORKS (DPW) JRBAN FORESTRY PERMITS & POLICY'S SIDEWALK LANDSCAPING GUIDELINES FOR MORE DEFAILED INFORMATION.

 SEE 2b FOR ENLARGED LAYOUT & SECTIONS.

Ģ

- 6. SEE 20 FOR ENLARED LAYOUT & SECTIONS.
 7. ENSURE TO MANTAIN 12" MINIMUM CLEAP OR PLANTED AREA ALONG BUILDING OOP PROPERTY LINE TO DETER PEDESTRANS FROM HITTING OBSTACLES WITHIN FRONTAGE ZONE.
- 8. SIDEWALK PLANTING SHALL NOT REDUCE THE ACCESSIBILITY OF THE SIDEWALK PAIH OF TRANEL ADVIG THE AREA OF WORK IS COMPARED TO THE EXISTING COMDITIONS. FOR EXAMPLE: IF THE EXISTING EDGE ZUNE AT CURB PROVIDES A PATH OF TRANEL THAT IS LESS THAN OR EQUAL TO ZX IN CROSS SLOPE, AND THE EXISTING PEDESTRIAN THROUGHWAY ZONE EXCEDS ZX CROSS SLOPE, THE ACCESSIBLE EDGE ZONE MAY NOT BE REDUCED WITH SIDEWALK LANDSCAPING UNLESS A NEW ACCESSIBLE PEDESTRIAN THROUGHWAY ZONE IS PROVIDED.

MANTAN A 48" WIDE ACCESSIBLE PATH TO SIDEMALK FIXURES, SUCH AS PEDESTRIAN DESIBILITIONS. CENTRALIZED PARKING METERS, MAIL BASES, AND FIRE AND POLICE PILL STATIONS. ASSON TOTE THAT THE ENTIRE WIGHT OF SIDEMAL FRONTING NEWBACKS MIST BE CLEAR OF OBSTRUCTIONS, AND A MINIMUM OF AT WIDE, BUT NOT MARROWER THAN NEWSRACK/NEWSTAND.



PLANTING ALONG CURBSIDES WITH PERPENDICULAR PARKING

OPTION C